

Jetline Construction  
1815 Mcdonald Ave.  
Royal Oak MI, 48073

# Estimate

Number E101

Date 11/14/2016

## Bill To

Donald King  
Indian Lake Improvement Association  
75 Ridgemont Rd  
Oxford MI, 48370

## Ship To

PO Number

Terms

Project

Indian Lake Dam freeze/thaw protection

Description

Amount

Install block wall with footing halfway up the height of the structure to hold sand in place, at the halfway point in each bay.

Truck an estimated 100yards of sand to the bays by way of both entry points to the dam. Backfill sand in each bay to the desired height taking in to consideration the water height on the opposite side of dam.

Truck an estimated 30 yards of top soil to the bays by way of both entry points to the dam. Cover the sand with top soil and pitch down and away from cement wall in order to add freeze thaw protection.

Seed the soil with grass in order to prevent wash out, and add longevity.

Add crushed stoned to bases of wingwalls to prevent future wash out and deterioration.

Price includes two skid steers, sand, top soil, grass seed, cement, masonry block, and all labor involved in the freeze/thaw phase of the dam project. \$22,000.00

Care will be taken so as not to disturb the ground on both of the adjoining properties of the dam. Afterwards, any disturbance to lawn or driveways will be repaired at no cost to homeowners.

Jetline Construction  
1815 McDonald Ave.  
Royal Oak MI, 48073

# Estimate

Number E101

Date 11/14/2016

**Bill To**

Donald King  
Indian Lake Improvement Association  
75 Ridgemont Rd  
Oxford MI, 48370

**Ship To**

PO Number

Terms

Project

Indian Lake Dam freeze/thaw protection

Description

Amount

Amount Paid \$0.00

Amount Due \$22,000.00

Discount \$0.00

Shipping Cost \$0.00

Sub Total \$22,000.00

Total \$22,000.00